BRUHATH BANGALORE MAHANAGARA PALIKE,
DASARAHALLI ZONE
Office of the Executive Engineer Dasarahalli Division

Schedule - B

BBMP/2020-21/OW/WORK_INDENT43849/CALL-2

NAME OF WORK: Improvements of CC drains covering slab in Krishnegowda layout cross roads in Dasarahalli ward no 15

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri VISHWANATHA	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Dismtling of existing structures like culverts, Bridges, retaining walls and other structure comprising of masonary, cement concrete, wood work,steel work, including T&P and scaffolding whereever necessary, sorting the dismanlet material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specification Lime/Cement concrete I. By Manual Means C. Prestressed /Reinforced cement concrete Grade M-20 & above	Cum	175.50	1000.0	Rupees One Thousand Only
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications	Cum	70.20	4000.0	Rupees Four Thousand Only
3	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification No.1600 & 2200	Tonne	7.37	70000.0	Rupees Seventy Thousand Only

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri VISHWANATHA	
				In Figures (Rs.)	In Words (Rs.)
4	Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3	Cum.	56.16	137.0	Rupees One Hundred Thirty Seven Only
5	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200	Cum	147.42	6500.0	Rupees Six Thousand Five Hundred Only
6	Providing and fixing precast RCC slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortar including from work lift charges, curing and concrete finished surface on both side etc.,	Sqm	185.40	1000.0	Rupees One Thousand Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	56.16	69.8	Rupees Sixty Nine and Eighty Paise Only

Signature of the Contractor,

Executive Engineer,
Dasarahalli Division,